BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/03/2014-15, Date:31.10.2014. **ITEM NO: 51**

SCHEDULE-B

NAME OF WORK: Maintenance of borewells at Sidedahalli village limit in Bagalagunte Ward No.14.

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor **B M YOGANANDA**	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Supply and delivery at site brand new Texmo / Innoval / Lubi / Sabar / Atalanta / Calamal / waterman / Radha make suitable vertical installation in 150mm dia. Borewells comprising of single stage or miultistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction mortor suitable for operation of 3Ph., 50Hz. 380/44 volts AC supply fitted with required accessories such as suction. casing, suction strainers, sand guard Non return valve etc., complete the pump and motor shall form an integral unit with all the required fittings 15HP 30 stage SE Complete as per specification and direction of Engineer-in-charge of the work.	No	3	70450.0	Rupees Seventy Thousand Four Hundred Fifty Only
2	Supplying and Drawing 3 core Flat PVC Shalted Submersible Pump Cable Manufactured with Electrolytic Grade Copper with Flexible copper conductor to table 3 class 5 of IS 8130-1984 and Virgen PVC insulation and Sheeated Suitable for working Voltage Upto 1100 Volts as per Page No:49 item No 29C/1 PREE- SR 2011-12	Mtrs	2000	150.0	Rupees One Hundred Fifty Only
3	Supplying and fixing 50mm Non Return Vavle of vertical type of approved make including cost of all materials labour HOM of equipment with all leads Complete as per specification and direction of Engineer-in-charge of the work.	Nos	10	1550.0	Rupees One Thousand Five Hundred Fifty Only
4	Supplying and fixing 50mm GM Gae Vavle Complete as per specification and direction of Engineer-in-charge of the work.	Nos	10	1050.0	Rupees One Thousand Fifty Only
5	Supplying and fixing 160mm Borewell cap with clampset Complete as per specification and direction of Engineer-in-charge of the work.	Nos	5	680.0	Rupees Six Hundred Eighty Only
6	Supplying and fixing 50mm GI Union Complete as per specification and direction of Engineer-in-charge of the work.	Nos	10	205.0	Rupees Two Hundred Five Only
7	Supplying and fixing 50mm GI Elbow Complete as per specification and direction of Engineer-in-charge of the work.	Nos	25	100.0	Rupees One Hundred Only

Signature of the Contractor

Executive Engineer

8	Supplying and fixing 50mm GI coller Heavy duty PRED Cc ɔlete as per specification and direction of Engineer-in-charge of the work.	Nos	250	135.0	Rupees One Hundred Thirty Five Only
9	Supplying and delivery at site brand new star / Essen / Lotus / Sun shines / Adharsh / GK Controls best indigenous make combined energy meter cum control panel board unit of size 1200x600x350mm minimum mechanically strong vermin and water proof. The unit shall have two detachable doors suitable for opration on 3ph, 50 hz, 380/440 volts, AC supply with spring loaded latch, locking device with a key ribs should be provided inside the door canopy apron and louvers ventilators shall be provided the combined energy meter cum control panel board unit suitable for operation on 3ph, 50 hz, 380/440 volts AC supply shall be consists etc., complete the panel board shall be consist etc., complete the panel board shall be fabricated on single unit in the above componenets panel board for suitable pumpset with star delta staretr out door type 10hp to 15 hp Complete as per specification and direction of Engineer-in-charge of the work.	Nos	5	9850.0	Rupees Nine Thousand Eight Hundred Fifty Only
10	Providing and fixing of 50mm G.I pipe 'C' class heavy duty foe erection of submersible pumpset Complete as per specification and direction of Engineer-in-charge of the work.	Mtrs	400	365.0	Rupees Three Hundred Sixty Five Only
11	Erection of combined panel board and meter unit with necessary materials and labour including providing cement concrete foundation bed cont door type etc., Complete as per specification and direction of Engineer-in-charge of the work.	Nos	5	455.0	Rupees Four Hundred Fifty Five Only
12	Supplying and fixing 500x500x65mm polished wood board made up not less than 15mm thick plank in front plank one end provided for olding at other end fixing the same of the valve using through bolts and nuts, Complete as per specification and direction of Engineer-in-charge of the work.	Nos	5	235.0	Rupees Two Hundred Thirty Five Only
13	Supplying, fixing and wiring heavy duty low voltage capacitors confirming to I 2834, 3 PHASE 400/440 Volts grade for power factor improvement of rotating machinery capacitor in KVAR - rating Nos 2 KVAR Capacity Complete as per specification and direction of Engineer-in-charge of the work.	Nos	5	315.0	Rupees Three Hundred Fifteen Only
14	Supplying and fixing miniature Circuit breakers on existing MCB distribution boards using necessary fixing materials and wiring Complete as per specification and direction of Engineer-in-charge of the work.	Nos	5	950.0	Rupees Nine Hundred Fifty Only
15	Supply 1.1 KV class UG cable from nearest BESCOM pole to panel board including earth work and road restoratio 4 core 16 sqmm. Complete as per specification and direction of Engineer-in-charge of the work.	Mtrs	100	125.0	Rupees One Hundred Twenty Five Only

Signature of the Contractor

1
Executive Enginee

16	Labour charges for laying 1.1 KV class UG cable when supplied by agencies in existing trenches GI pipe / stoneware pipe/ on pole as required, Complete as per specification and direction of Engineer-in-charge of the work.	Mtrs	100	3.0	Rupees Three Only
17	Digging of trench of 0.6m deep x 0.5m wide refilling the trench to the required level and consolidating etc., Complete as per specification and direction of Engineer-in-charge of the work.	Mtrs	75	44.0	Rupees Forty Four Only
18	Supplying and fixing of porcelain fuse channel with cut-out on existing / new wooden panel using neccesary nuts, bolts and washers etc., complete P-32, I-3 (b), PWD ELECTRICAL SR 2010-11.	Nos	50	200.0	Rupees Two Hundred Only
19	Earthwork excavation for foundation of buildings water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods Complete as per specification and direction of Engineer-in-charge of the work.	Cum	229.5	240.0	Rupees Two Hundred Forty Only
20	Providing and installing at site of work P.V.C pipees including cost of pipes and specials and labour including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe alround to a depth not leass than 15 cms with gravel or selected earth available from the excavation etc., Complete as per specification and direction of Engineer-in-charge of the work.	Rmt	425	150.0	Rupees One Hundred Fifty Only
21	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5m. Including cost of all labour Complete as per specification and direction of Engineer-in-charge of the work.	Cum	229.5	49.0	Rupees Forty Nine Only
22	Transportation of pumping machineries Complete as per specification and direction of Engineer-in-charge of the work.	No	8	840.0	Rupees Eight Hundred Forty Only
23	Erection of Pumping machineries Complete as per specification and direction of Engineer-in-charge of the work.	No	8	840.0	Rupees Eight Hundred Forty Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,